

WIFI AUTOMATION – ROBOT AUTOMATION – USER MANUAL

Bell Canada; ATL Lab



Contact:

Angelo Virgilio

Angelo.virgilio@ecin.ca

Mobile: 416.605.1296



Revisions

Version	Primary Author(s)	Description of Version	Date Completed
0.1	Arijit Saha	First Draft version	May 30, 2017
0.2	Angelo Virgilio	Added template, formatted and updated various sections	June 2, 2017
0.3	Angelo Virgilio	Added New Section - Next steps	June 7, 2017
1.0	Arijit Saha	User Manual – Complete description for MySQL Project	Aug 15, 2017
2.0	Arijit Saha	Final Version – Robot Automation Project (Integrated)	Oct 18. 2017

Review & Approval

Requirements Document Approval History

Approving Party	Version Approved	Signature	Date
Bell Canada: Bertrand Camus Intissar Harrabi	0.3		

Requirements Document Review History

Reviewer	Version Reviewed	Signature	Date
Angelo Virgilio	0.3		June 9, 2017



Contents

1.	Open RIDE GUI	4
2.	Load Project in RIDE	5
3.	Test Suite Management	9
4.	Test Case Management	10
5.	Configuring Result Arguments	11
6.	Configuration and Execution of MySQL Store Result test case	12
7.	Truncate data from tables in database	15
8.	Configuration for Predefined TestCases All	18
9.	Configuration for User Defined Test Suite	19
10.	Test Case Copy and Reorder	20
11.	Configuring Common Parameter	21
12.	Generate TestCases Test Suite	23
13.	Generate TestCases_ALL Test Case	24
14.	Configuring Test Parameters	25
15.	Running "Generate_TestCases" test suite.	26
16.	Test Parameter Validation	27
17.	Test Parameter Dependency Validation	28
18.	Running "Generate_TestCases" test suite.	29
19.	Test Command Generation Directory	30
20.	Test Command Generation	31
21.	Generate_TestCases_All test case Execution Progress	32
22.	Selecting Test cases to Execute	33
23.	SSH and SCP to Wave Automation Server	34
24.	Detecting test case completion and failure in Wave Automation	35
25.	Storing Wave Automation test case execution time	36
26.	Finding Wave Automation test case execution time	37
27.	Executing TP test cases (dynamic)	38
28.	Selecting Test cases for execution	39
29.	Getting Wave Automation timestamp result directory name	40



30.	MySQL Integration	41
31.	Obtain Loads dynamically for LAT and RR test cases	42
32.	Executing LAT test cases (dynamic)	43
33.	Executing RR test cases (dynamic)	44
34.	Executing MaxClient test cases (dynamic)	45
35.	Creating and selecting user defined test cases for execution	46
36.	ROBOT Automation execution time	48
37.	Saving PCAP files	49
38.	Enabling Debug	50
39.	Test Execution Progress	51
40.	Robot Automation Post Execution Logs	52
41.	Robot Automation test report	53
42.	Configuring Backup Script	54
43.	Executing Backup Script	56
44.	Configuring Copy Script	57
45.	Executing Copy Script	58
46.	Database Backup	59
47.	MySQL Database Management	60
48.	MySQL Script Execution Progress	64
49.	MySQL Script Post Execution Logs	65




1. Open RIDE GUI

In order to view and execute the test cases, the user needs to open the RIDE GUI from the shortcut named "ROBOT Automation RIDE" which is present on the Desktop.

a. Double click on the shortcut icon to open the RIDE GUI.



b. RIDE GUI should open.




Note: Creation of shortcut has been mentioned in the installation document section 2.7.1.



2. Load Project in RIDE

After the RIDE GUI opens, the user needs to load the project folder so that they get the view of the test case structure and the different test cases that are present for execution.

- Copy the "Bell HomeHub Automation DB Creation.zip" provided along the document to root folder "C:\".
- Extract the folder to "C:\" as shown.




• After extracting the folder, a list of folders as shown in below picture should be present.






• Now on the RIDE GUI, click on "File" and click on "Open Directory" to open the file system and choose the project to be loaded from local folder.




• From the window that opens, click to expand the contents of drive "C:\".






• After the contents of the driver expand, click on "Bell HomeHub Automation" folder again to expand and show the contents.




• As the folder contents expand, click on "Bell_HomeHub_Automation" folder to select. Click "Ok" button.






• The RIDE GUI will have the contents loaded as shown.






3. Test Suite Management

a. Right-click on project name which will be there on the top left of the screen and click on "New Suite" option.




b. In the box that appears, enter the name of the Test Suite, select radio button "File" for Type and "ROBOT" for Format.






4. Test Case Management

a. Right-click on test suite name and click on "New Test Case" option.



b. Enter the test case name in the window that pops up and click on Ok button.






5. Configuring Result Arguments

The section aims to customize the result files name, location and the background colour.


Command: "-d ..\\Bell_HomeHub_Automation_Results --timestamp -- reportbackground white:white"

The above command needs to be inserted in the arguments section, following the steps:


a. Click on project name.




b. Click on **Run** tab.



c. Copy the above mentioned command and paste it in arguments text area as shown.



d. Select **Execution Profile** as **pybot** (if not already selected).




e. Click to checkbox to mark as selected for **Show message log** (if not already selected).






6. Configuration and Execution of MySQL Store Result test case

a. Click on "Database Scripts" test suite and expand to view the test cases in it.



b. Click on "MySQL Store Result" to select. On the right half of the screen, the Edit tab will open and show the contents as seen in the picture below.





- c. Configuration for the test cases include:
 - **Test Name** Name of the test case. Example –> AC-TP-80MHz.
 - Location of .bat file Location of .bat on Wave Automation Server for the test case mentioned above. Example-
 - >C:/lxVeriwave/automation4.6/automation/conf/H3000/HH3000-Rel1_2_3-auto_conf.bat.


Note: File path should contain front slash only as shown in example and should contain name of .bat file.

- **Direction** Direction mentioned in the test case. Example -> DS for Downstream.
- Result TimeStamp

 TimeStamp created during the test execution for storing results for the particular test case. Example-> 20170519-142612.
- **Throughput Multiplier** Value for throughput multiplier applicable for TP test cases only. Other test cases have value 0.


Enter values for each row for the test cases that needs to be executed.

d. Select the MySQL Store Result test case by clicking on the checkbox on the left of it.





e. Click on Run button to start execution of the test case.







7. Truncate data from tables in database

NOTE: TRUNCATE operations cannot be undone or rolled back.

a. Click to select the tables that need to be truncated from the Navigator window on the left pane of MySQL Workbench.




b. Right click the mouse button keeping the pointer on the selected table names. A menu box will appear.






c. Click Truncate Tables options present on the pop up menu bar.

Note: The number of tables to be truncated will be shown which will depict the number of tables selected. For example it shows "Truncate 8 Tables" in the picture below.




d. Click Truncate on the confirmation box.





e. It might take a couple of seconds based on the amount of data to be truncated. Upon refreshing/ reopening the table contents, a clear table will be seen.







8. Configuration for Predefined TestCases All

Note: There are 8 test suites named by the type of test cases they have in them. For example:

a. Click on "TS1_Throughput_5G" test suite and expand to view the test cases in it.



b. Click on "TS2_Throughput_2.4G" test suite and expand to view the test cases in it.




c. Click on any other test suites present in the left block. The user will be able to see two test cases of the particular type present under each of the test suites.




9. Configuration for User Defined Test Suite

a. Click on "User1 TestSuite" test suite and expand to view the test cases in it.



b. Click on "AC-TP-80Mhz3" to select. On the right half of the screen, the Edit tab will open and show the contents as seen in the picture below.




c. Enter the values as mentioned in the labels above for each.




10. Test Case Copy and Reorder

a. Click on Test Case Name that needs to be copied and drag it to the test suite to copy to.



b. To reorder, select a test case and right click on it. Click on Move Up/ Move Down option.






11. Configuring Common Parameter

User can enter common parameters values that are used by all test suites and test cases in userconfig.txt file.


a. The label for the parameter will be present on the right under comments column, followed by the description of the same.



b. The default value for the parameter will be present under **Value**column. Click on the row to enter the modified value for the particular parameter. It opens a pop up window.



c. In the text box for **Value**, remove the default value and type in the actual value for the environment. Click Ok.





d. In the similar way, all the parameters present in the file as shown below can be configured by the user.

Variable	Value	Comment
\${var_wahostname}	10.66.41.2	# WA Host Name - Hostname of the Wave Automation Server
\${var_wausername}	wave-automation1	# WA User Name - Username of the Wave Automation Server
\${var_wapassword}	Fa\$terThanL1ght	# WA Password - Password for the Wave Automation Server
\${var_waportnumber}	22	# WA Port Number - Port Number for SCP to Wave Automation Server
\${var_dbhostname}	localhost	# DB Host Name - Host name for Database server
\${var_dbusername}	root	# DB Username - Username for DB connection
\${var_dbpassword}	bell	# DB Password - Password for the DB connection
\${var_localDBBackup}	/Bell_HomeHub_Automation/Bell_HomeHub_Automation_Ba	# Local DB Backup - Location on DB Backup files in Robot Server
\${var_localDBBackup}	/Bell_HomeHub_Automation/Bell_HomeHub_Automation_Ba	# Local DB Backup - Location on DB Backup files in Robot Serv



12. Generate TestCases Test Suite


Generate TestCases Test suite contains the list of all Test cases and Test parameters needs to be passed to create test commands.

In order to create the suite, the user needs to follow the steps.


a. Right click on the name of the project and click on New Suite.



As the window appears type in "Generate TestCases" in the pop up window.
 Click Robot radio button to specify the format.



c. User will be able to see a test cases being created under the project.






13. Generate TestCases ALL Test Case


Generate_TestCases_All creates test commands for all test cases per user configuration for Throughput, Latency, Rate_vs_Range and MaxClient.

The user needs to create the test case file under the **Generate_TestCases** test suite. In order to create the suite, the user needs to follow the steps.


1. Right click on **Generate_TestCases** test suite and click on **New Test Case**.



2. Enter the name of the test case in the box that appears and click Ok.



3. User will be able to see a test case being generated under the test suite.



4. After creating Generate_TestCases_All in Setup enter following command. "Run Keywords | SetUserConfig | AND | SetExecutionMode | Auto" Which will setup the required parameters for execution.





14. Configuring Test Parameters

Users will be able to enter test parameters that are specific for creating test commands for the mentioned test cases.

a. Users can enter the values based on the labels mentioned at the top for **Library**

1	Set Test Documentation	To generate the test case				
	Library Command	Tests Name (mention the test case Name)	Test Type (select from TP, RR, Lat or MaxClient)	Direction (Bi-Direction = 1 / Uni-Direction = 0)	Band Selection (2.4 / 5)	Channel
-						


b. User will be able to click on the cell and type in the value where each row refers the data for a .bat file.

	,	Test Type (select from TP, RR, Lat or MaxClient)		Direction (Bi-Direction = 1 / Uni-Direction = 0)	Band Selection (2.4 / 5)	Channel
CreateTestCommand	AC-TP-5G-80MHz4-4ss-36c	TP	Auto	1	5	36



15. Running "Generate_TestCases" test suite.

- a. User needs to configure the parameters for the Generate_TestCases test suite as shown. (Refer 13. Configuring Test Parameters)
- b. Select the checkbox for "Generate_TestCases_All" test case under "Generate_TestCases" test suite as shown in figure and click Run button.





16. Test Parameter Validation

- a. User clicks on Run button to execute "Generate_TestCases_All" test case.
- Robot Automation will check to validate all input test parameters entered by the user at the time of configuration. Ex: as shown in picture below, the value for Band Selection is invalid.

To generate the test case combination for All					
Tests Name (mention the test case Name)	Test Type (select from TP, RR, Lat or MaxClient)	Load Mode (Auto/Manual)	Direction (Bi-Direction = 1 / Uni-Direction = 0)	# Band Selection (2.4 / 5)
AC-TP-5G-80MHz4-4ss-36c	TP	Auto	1	8	
	TP	Auto	0	5	
AC-Lat-5G-80MHz4-4ss-36c	LAT	Auto	1	5	
	combination for All Tests Name (mention the test case Name) AC-TP-5G-80MHz4-4ss-36c	combination for All Tests Name (mention the test case Name) Test Type (select from TP, RR, Lat or MaxClient) AC-TP-5G-80MHz4-4ss-36c TP TP	combination for All Tests Name (mention the test case Name) Test Type (select from TP, RR, Lat or MaxClient) AC-TP-5G-80MHz4-4ss-36c TP Auto Auto	combination for All Tests Name (mention the test case Name) Test Type (select from TP, RR, Lat or MaxClient) Load Mode (Auto/Manual) Direction (Bi-Direction = 1 / Uni-Direction = 0) AC-TP-5G-80MHz4-4ss-36c TP Auto 1 TP Auto 0	combination for All Tests Name (mention the test case Name) Test Type (select from TP, RR, Lat or MaxClient) Lat or MaxClient) Load Mode (Auto/Manual) Direction (Bi-Direction = 1 / Uni-Direction = 0) # Band Selection (2.4 / 5 / Uni-Direction = 0) AC-TP-5G-80MHz4-4ss-36c TP Auto 1 8 TP Auto 0 5

c. When Robot Automation finds a value entered by used is not in range or is invalid, it will show the error and abort the Test Case generation process.

```
FrameSize Parameter value is Valid
FrameSize Parameter value is Valid
Expected Connection Parameter value is Valid
Source Parameter value is Valid
Destination Parameter value is Valid
Channel Parameter value is Valid
SS Parameter value is Valid
Channel Bandwidth Parameter value is Valid
Guard Interval Parameter value is Valid
pcap Parameter value is Valid
  ***:CTC!!!!! Test Farameter Validation Failed please check the logs for more details
Please choose Either 2.4Gz or 5Gz band
```

d. After the validation check, if no errors for parameters entered are found, the logs will show a success message.


```
SS Parameter value is Valid
Channel Bandwidth Parameter value is Valid
Guard Interval Parameter value is Valid
pcap Parameter value is Valid
*****CTC****** Parameter Validations are done all parameters are valid
******PDV****** Validating Dependency Band Selection is 5 and Source/Destination = W_AC
******PDV***** MCS in desired range
******PDV***** Channel is in desired range
******PDV***** Channel is in desired range
Bandwidth is in desired range
Bandwidth is in desired range
******CTC****** Parameter Dependancy check are done Successfully
Ending test: Bell HomeHub Automation.Generate TestCases.Generate TestCases All
```



17. Test Parameter Dependency Validation

User can configure various test types in the Generate_TestCases_All test case. When the user enters the values, the dependent test parameters will also be checked.


- a. The user enters values to configure test command for TP test cases. The values like "ss", "mcs" and "framesize" are the test case dependent values.
- b. When the user enters test case parameter values for LAT or RR, Robot Automation will check the values for "ss", "mcs" and "framesize" which should be same or a subset of the values for the equivalent TP test cases parameter values.
- c. Robot Automation will validate the values and show error log on the screen when the values are not in valid range. Robot Automation will show success when the values are in expected valid range.





18. Running "Generate_TestCases" test suite.

After configuring test parameters select the "Generate_TestCases" test suite as shown in figure and click on Run button.




When user click on Run button, Robot Automation Framework first validates the input test parameters and if any value entered by used is not in range framework will highlight the error and abort the Test Case generation process.

After Test parameter validation succeeded Robot Automation Framework will execute the Parameter Dependency validation check. If Parameter Dependency check failed then Framework will highlight the error and abort the execution Process




19. Test Command Generation Directory

Upon successful validation of test parameters and dependencies entered by user, the Test command directory will be created. To create the directory, user needs to set the value of "SetExecutionMode" to "Auto".



The test command files will get stored under following project directory "Bell_HomeHub_Automation\Bell_Homehub_Automation_TestCommand". A new directory will be created named by execution timestamp value in format "TC_<YYYYMMDD-HHMMSS>".




For every execution of "Generate_Testcases_ALL" test case, ROBOT Automation will create a new directory with current timestamp and store test command files in it as shown above.



20. Test Command Generation

Upon successful validation of test input values by the user, a directory with current execution timestamp value will be created and the test command files will be stored in it. The test command files created will be based on the user input values and the user will be able to enter values to create four types of test command files as mentioned below:

- 1. Throughput (TP)
- 2. Latency (LAT)
- 3. Rate Vs. Range (RR)
- 4. MaxClient.






21. Generate_TestCases_All test case Execution Progress

When user starts execution by pressing "Run" button, the execution progress will be shown to the user along with the logs in details

The processes that will execute on starting it are:

- a. Validation of user input values and dependencies.
- b. Creation of test command directory to store the files named by current timestamp.
- c. Creation of test command and stored in the folder in particular folder created.

For details refer following figure.



The execution status will show "Pass" when all the points mentioned above will get executed properly.




22. Selecting Test cases to Execute

ROBOT Automation provided options for users to select the list of test cases to execute as shown in the figure below.

User can select both "Generate_Testcases_ALL" test case along with actual test cases below like N-TP-2.4G-40MHz-4ss-11c and execute them, or execute

"Generate_TestCases_All" and then select specific test cases to execute individually.





23. SSH and SCP to Wave Automation Server

When user selects test case for execution, ROBOT Automation will create the .bat command file in

"Bell_HomeHub_Automation\Bell_Homehub_Automation_TestCommand" as shown in section 20.

The generated .bat will be copied to Wave Automation server using the "Secure Copy" method, i.e. SCP. Once the .bat command file is copied on server, the respective command for the test case in the .bat file will start to execute.

In order to execute the command file on Wave Automation server, ROBOT Automation framework will create secure SSH connection between them and start execute the command file on the Ixia chassis. User will be able to configure the server details and SSH details for the execution to take place in the userconfig.txt file (Refer Section 11 Configuring Common Parameter).



24. Detecting test case completion and failure in Wave Automation

After copying .bat command file on Wave Server, ROBOT Automation framework will execute the command file. During the execution of the command file on the Wave Automation server, a temporary file will be created to fetch the details getting printed on the console.

On completion of the execution, ROBOT Automation framework will again copy the temporary file created from Wave Automation server and parse it.

The application will parse every line of the file so that It gets all the necessary details from it. It will fetch details like:

- a. Duration of test case execution on Ixia Server.
- b. Location of result files
- c. Status of the test execution.



25. Storing Wave Automation test case execution time

For each executed test case, the time taken to execute (test duration) of the test case is calculated and it stored in text file temporarily. The value will be visible to the user in the database on a permanent basis.

Upon integration with MySQL Store Script. the value will also be placed in the database where under "test_duration" column in 'wifi_test_param_main' table.



26. Finding Wave Automation test case execution time

ROBOT Automation Framework will parse the execution log file to identify the total execution time. The logic is explained below:

```
#### Starting automated test run at 20170519-150123 - (Store in
<var_testcase_starttime> )
#### Automated test run completed at 20170519-151121 - (Store in
<var_testcase_endtime>
```

Then calculate the test duration:

<var_testdutation> = <var_testcase_starttime> - <var_testcase_endtime>



27. Executing TP test cases (dynamic)

Note: Execution of TP test cases is a must before executing corresponding LAT and RR test cases. Steps to execute TP test case is explained below:

Let us consider AC-TP-80MHz3 user test case, the logic that will be implemented for execution are:


- ROBOT Automation will look for the latest folder created (named by timestamp)
 under
 - "Bell_HomeHub_Automation\Bell_Homehub_Automation_TestCommand".
- Check for '.bat' files created based on the number of commands entered in "Generate_Testcases_ALL" test case. It will proceed with execution if the file is present, else shows an error to the user.
- Secure copy the .bat file created to the Wave Automation Server and place it in the directory for the execution on Ixia chassis.
- 4. Establish secure connection and execute the .bat file over SSH.
- 5. Detection of completion status of the execution. A successful execution status will make the ROBOT Automation carry on with the following tasks, else will show an error to the user, stating the reason on a failure.



28. Selecting Test cases for execution

ROBOT Automation will allow user to select individual or group of test cases within a test suite or multiple test suites for execution and click on "Run" to execute them.

User can select test cases to generate test commands and execute. The sample screenshot is shown below.





29. Getting Wave Automation timestamp result directory name

ROBOT Automation will read the data that gets printed on the console while the test case gets executed over SSH. The entire data of the prompt will be redirected to a temporary file that will be created called output.log.

ROBOT Automation securely copies the file from the Wave Automation server and reads the entire contents. The timestamp folder where the results values will be found, is parsed and fetched from the file itself.

```
IPv4toInt() input error: 1 is not in the form x.x.x.x
IPv4toInt() input error: 1 is not in the form x.x.x.x
IPv4toInt() input error: 1 is not in the form x.x.x.x
Completed: Report C:/wifiResults/HH3000/testtest/BELL368/TP/D$/20170828-015538/unicast_unidirectional_through
Thank you for using Veriwave (http://www.veriwave.com)
### END run of testcase 2
### END Testcase 2
### Testcase 2
### Testcase 2 Passed at 20170828-020228.
### Intermediate Results: PASS: 2 FAIL: 0 ABORT: 0 Skipped: 0
```



30. MySQL Integration

ROBOT Automation will integrate the MySQL scripts where the data from the results file will be stored into the database automatically after execution of the test command on the Wave Automation server.

When the execution of the test case completes on the Wave Automation server, the output.log file will be parsed and the folder where the results are stored will be fetched.

Then the MySQL Store Result script will be called automatically which will extract the data from the .bat files and store in the respective tables. The corresponding result .csv files will also be fetched and parsed.


After the data is fetched and calculations are done if required, the fetched data from the result .csv files will be stored in the database.



31. Obtain Loads dynamically for LAT and RR test cases

To obtain the value for loads field in LAT and RR, the user needs to execute the corresponding TP test case first. For example, if the user plans to execute "N-LAT-2.4G-40MHz-1ss-1c-7mcs", first the execution of "N-TP-2.4G-40MHz-1ss-1c-7mcs" needs to be carried out. Upon successful execution of the corresponding TP test case, the value of "throughput_pps" will be extracted.

Value of "threshold_throughout_pps" will be calculated which is usually 90% of throughput_pps, else will be calculated based on the input provided by user for "throughput" field when configuring the TP test case.



Loads for LAT and RR will be the value of "threshold_throughout_pps" for corresponding TP test case, where the value will be extracted for **each frame size against each MCS** value.

For example, **N-TP-2.4G-40MHz-1ss-1c-7mcs** has frame size values "1512 1024 512 64", and has only one MCS value which is "7", so **N-LAT-2.4G-40MHz-1ss-1c-7mcs** will have ,loads value for each frame size present in the corresponding TP test case per MCS. So **N-TP-2.4G-40MHz-1ss-1c-7mcs** will have 4 loads values.



32. Executing LAT test cases (dynamic)

Note: Execution of corresponding TP test cases is mandatory before executing a LAT test case. Steps to execute TP test case has been explained above, in section 27.

Let's consider **N-LAT-2.4G-40MHz-1ss-1c-7mcs** test case to be executed, the logic that will be followed for execution are:

- ROBOT Automation will look for the latest folder created (named by timestamp) under
 - "Bell HomeHub Automation\Bell Homehub Automation TestCommand".
- 2. Check for '.bat' files created based on the number of commands entered in "Generate_Testcases_ALL" test case. It will proceed with execution if the file is present, else shows an error to the user.
- Robot Automation will check the successful execution of corresponding TP test case before execution of LAT test case. If it finds a successful execution, then it proceeds to execution LAT else shows an error to the user.
- 4. Robot Automation will extract "threshold_throughput_pps" value from database for writing the loads value to the .bat file created for LAT test case.
- Secure copy the .bat file created to the Wave Automation Server and place it in the directory for the execution on Ixia chassis.
- 6. Establish secure connection and execute the .bat file over SSH.
- 7. Detection of completion status of the execution. A successful execution status will make the ROBOT Automation carry on with the following tasks, else will show an error to the user, stating the reason on a failure.
- The MySQL scripts will be called automatically after successful execution of LAT
 test case of Ixia chassis. MySQL scripts will store data from .bat file in database and
 also fetch data from Result files for the particular execution and store them in
 database.



33. Executing RR test cases (dynamic)

Note: Execution of corresponding TP test cases is mandatory before executing a RR test case. Steps to execute TP test case has been explained above, in section 27.

Let's consider **N-RR-2.4G-40MHz-1ss-1c-7mcs** test case to be executed, the logic that will be followed for execution are:

- 1. ROBOT Automation will look for the latest folder created (named by timestamp) under "Bell_HomeHub_Automation\Bell_Homehub_Automation_TestCommand".
- Check for '.bat' files created based on the number of commands entered in "Generate_Testcases_ALL" test case. It will proceed with execution if the file is present, else shows an error to the user.
- Robot Automation will check the successful execution of corresponding TP test case before execution of RR test case. If it finds a successful execution, then it proceeds to execution RR, else shows an error to the user.
- 4. Robot Automation will extract "threshold_throughput_pps" value from database for writing the loads value to the .bat file created for RR test case.
- 5. Secure copy the .bat file created to the Wave Automation Server and place it in the directory for the execution on Ixia chassis.
- 6. Establish secure connection and execute the .bat file over SSH.
- 7. Detection of completion status of the execution. A successful execution status will make the ROBOT Automation carry on with the following tasks, else will show an error to the user, stating the reason on a failure.
- 8. The MySQL scripts will be called automatically after successful execution of RR test case of Ixia chassis. MySQL scripts will store data from .bat file in database and also fetch data from Result files for the particular execution and store them in database.



34. Executing MaxClient test cases (dynamic)

Let's consider **N-MaxClient-2.4G-40MHz-1ss-1c-7mcs** test case to be executed, the logic that will be followed for execution are:


- 1. ROBOT Automation will look for the latest folder created (named by timestamp) under "Bell_HomeHub_Automation\Bell_Homehub_Automation_TestCommand".
- 2. Check for '.bat' files created based on the number of commands entered in "Generate_Testcases_ALL" test case. It will proceed with execution if the file is present, else shows an error to the user.
- 3. Secure copy the .bat file created to the Wave Automation Server and place it in the directory for the execution on Ixia chassis.
- 4. Establish secure connection and execute the .bat file over SSH.
- 5. Detection of completion status of the execution. A successful execution status will make the ROBOT Automation carry on with the following tasks, else will show an error to the user, stating the reason on a failure.
- 6. The MySQL scripts will be called automatically after successful execution of MaxClient test case of Ixia chassis. MySQL scripts will store data from .bat file in database and also fetch data from Result files for the particular execution and store them in database.




35. Creating and selecting user defined test cases for execution

User will be able to create a Test Case from the RIDE GUI.

1. ROBOT Automation will let the user create the Test Commands by configuring the values for the test cases in Generate_TestCases_All file from RIDE GUI.



2. User can either provide a name for the .bat file that will be generated, else ROBOT Automation will create the name of the .bat file using the parameters provided by the user. For example in the picture shown, ROBOT Automation will create a .bat file by the "CustomName" as entered by user during the creation of .bat file and the second one will be created in the format specified by ROBOT Automation using the parameters entered like "N-LAT-2.4G-40MHz-1ss-1c-7mcs".




3. Now, the user needs to create a new test case in RIDE GUI (refer Section 4). The user will have to provide the name of the test case by the name of the .bat file created. For example, if the .bat file has been created as "CustomName.bat", then the name of the test case should be "CustomName" and the scenario remains the same if the bat file is named as "N-LAT-2.4G-40MHz-1ss-1c-7mcs".




4. User will have to configure certain values in the editable section for the test cases to run. In **Setup** section, "Set User Config" needs to be placed. User can click on the text box and type in the text in the box that appears.

Set Execution Mode needs to be set as Auto.

Execute Test Command needs to be called as shown below for execution of .bat file.



5. User will be able to execute a test case by selecting the check box on the left and clicking on Run button.






36. ROBOT Automation execution time

User will be able to check the total time taken for each test case to execute on the Ixia Veriwave chassis. The total time will be calculated based on the start time of the execution of each test case from the Robot Automation server. The test case will execute on the Ixia server and after completion Robot Automation will record the completion time too.

The difference will be calculated for each execution and the value will be stored in the database in "wifi_test_param_main" table under column "test_duration".







37. Saving PCAP files

User will be able to check PCAP files for each execution. The feature has been made configurable for the user.

The user will be able to configure the value either in "YES" or "NO" when creating the .bat files for each test case from "Generate_TestCases_All" test case.

roup Type	Save PCAPS	Throughput Multiplier
02.11ac	YES	0.9



38. Enabling Debug

User will be able to check "debug" parameter in each test command file.

On opening the .bat file created, the user will be able to get the debug parameter configured for the test case.

```
|::N-TP-2.4G-40MHz-1ss-11c-7
tclsh ..\..\bin\vw_auto.tcl -f TP.tcl
--var ssid "BELL368" ^
--var pw "testtest" ^
--var save "C:\wifiResults\HH3000\tes
--var ap "HH3000" ^
--var apver "testtest" ^
--var channel "11" ^
--var frameSize "1518" ^
--var loads "" ^
--var expectConn "" ^
--var expectConn "" ^
--var destination "ETH" ^
--var duration "5" ^
--var duration "5" ^
--var ss "1" ^
--var ss "1" ^
--var bw "40" ^
--var gi "short" ^
--var eth_dut "generic_dut_1" ^
--var w_dut "generic_dut_0" ^
--var w_grouptype "802.11ac" ^
--savencans ^
--debug 2
::
```



39. Test Execution Progress

User will be able to check the execution progress of the selected test case on the "message log" section of the RIDE execution window.

The progress logs will be shown in a specified format which will help the user understand the portion of the execution which is under progress.

The specified format is:

<Time> : <Log Level> : <Library Name> -> <Method Name> :: <Log message>

```
To generate the test case combination for All 20171002 10:39:24.621 : INFO : GenerateTestC
                                                                GenerateTestCaseLibrary.py -> CreateTestCommand ::
                                                                                                                                                                        Value for Throughput has been set to : 0.9
20171002 10:39:24.621
                                                  INFO : GenerateTestCaseLibrary.py -> CreateTestCommand ::
                                                                                                                                                                        Single MCS value have been provided for comma
20171002 10:39:24.621
                                                  INFO : GenerateTestCaseLibrary.py -> CreateTestCommand ::
                                                                                                                                                                       Custom Test Case Name has not been provided h
20171002 10:39:24.621
                                                  INFO : GenerateTestCaseLibrary.py -> CreateTestCommand ::
                                                                                                                                                                        Automatically generated Test Case Name is :
20171002 10:39:24.621
                                                  INFO : GenerateTestCaseLibrary.py -> CreateTestCommand :: Initiating Validation of Test Parameters.
                                                  INFO :
20171002 10:39:24.621
                                                                TestParameterValidationLibrary.py -> parameterValidation :: Starting Test Parameter Validation
20171002 10:39:24.621
                                                  INFO
                                                                TestParameterValidationLibrary.py -> parameterValidation :: Parameters for Test Type has been va
20171002 10:39:24.621
                                                                TestParameterValidationLibrary.py -> parameterValidation :: Parameters for Load Mode has been va
20171002 10:39:24.621
                                                  INFO
                                                                TestParameterValidationLibrary.py -> parameterValidation :: Parameters for Direction has been va
20171002 10:39:24.621
                                                  INFO
                                                                TestParameterValidationLibrary.py -> parameterValidation :: Parameters for Band Selection has be
20171002 10:39:24.621
                                                                TestParameterValidationLibrary.py -> parameterValidation :: Parameters for Expected Channel has
20171002 10:39:24.621
                                                  INFO
                                                                TestParameterValidationLibrary.py -> parameterValidation :: Parameters for FrameSize has been va
20171002 10:39:24.621
                                                   INFO
                                                                TestParameterValidationLibrary.py -> parameterValidation :: Load Mode Parameter has been validated
                                                                TestParameter Validation Library.py \rightarrow parameter Validation :: Parameters for Source has been validation in the parameter Validation of the validation of the parameter Validation of the validation of t
20171002 10:39:24.631
                                                   INFO
20171002 10:39:24.631
                                                  INFO
                                                                TestParameter Validation Library.py \rightarrow parameter Validation :: Parameters for Destination has been
 20171002 10:39:24.631
                                                   INFO
                                                                 TestParameterValidationLibrary.pv -> parameterValidation ::
                                                                                                                                                                                          Parameters for Channel has been val
```



40. Robot Automation Post Execution Logs

User will be able to check the logs of the current execution from the message log section as shown above. For any further reference of the shown logs, user will be able to fetch the same from the folder

C:\Bell_HomeHub_Automation\Bell_HomeHub_Automation_Results folder. The files will be named as **log-<YYYYMMDD>-<HHMMSS>.html**.

User will be able to open the log from RIDE by clicking on the button shown in the picture.



A detailed log file is also being created in the background for every execution. User will be able to open the file and read the contents for any clarification process. The file will be generated on a daily basis and will record all the execution data of the entire day in a single file.


The file will be available as:

C:\Bell_HomeHub_Automation\Bell_HomeHub_Automation_Results\DetailedLog_ < YYYYMMDD>.log




41. Robot Automation test report

User will be able to check the report and status of the current execution from the execution window in RIDE.



For the details report of the execution, user can click on the Report button on the RIDE and the report file will open in the default browser.







42. Configuring Backup Script

User will be able to configure the values for Database Backup script.

There are two modes in which the backup script will work and the configuration will be as follows:

1. Automatic Backup Mode

The parameters for the automatic backup mode are:

- a. Remote Location to store DB Backup The parameter will accept the location where the user chooses to store the Backup files of the database on the Wave Automation Server (remote server). For example: C:/DatabaseBackUp/
- b. Backup Type This is where the user chooses the mode of backup out of Automatic or Manual that they want to execute. The user should enter Automatic for this tag when executing Automatic backup.
- c. Backup Period (In Days) This is the value is applicable for Automatic backup type only where it determines the interval at which the scheduled backup task will execute on the Robot Automation server.
- d. **Backup Action** This value is applicable for Automatic Backup type only and where the expected values are Start and Stop.
 - **Start** This is to create a scheduled automatic backup task.
 - **Stop** This is to delete an existing scheduled automatic backup task.

/SQL_Backup	/C:/DatabaseBackUp/	Automatic	1	Start



2. Manual Backup

The parameters for the automatic backup mode are:

- a. Remote Location to store DB Backup The parameter will accept the location where the user chooses to store the Backup files of the database on the Wave Automation Server (remote server). For example: C:/DatabaseBackUp/
- b. Backup Type This is where the user chooses the mode of backup out of Automatic or Manual that they want to execute. The user should enter Manual for this tag when executing manual backup.

The other tags can be filled but the values in them will not be used now

1	" "	Remote Location to store DB Backup file	Васкир Туре	Backup Period (In Days)	Backup Action
2	MySQL_Backup	/C:/DatabaseBackUp/	Manual	1	Start
3					

Configuring server parameters to store Database Backup Files

- a. User needs to configure the values for the variables in userconfig.txt file.
- b. The values for server configuration include: **Host Name**, **Username**, **Password** and **SCP Port Number**.

\${var_backuphostname}	52.14.193.76	# DB BackUp Host Name - Hostname for server to store Database Backup
\${var_backupusername}	Administrator	# DB Backup User Name - User Name for server to store DB Backup
\${var_backuppassword}	bellserver2!	# DB Backup Password - Password for server to store DB Backup
\${var_backupportnumber}	22	# DB Backup SCP Port - Port Number for SCP to store DB Backup




43. Executing Backup Script


a. User will be able to execute the Backup Script by selecting the checkbox for the Backup script and after the configuration of the values have been completed.



b. Click on Run button after choosing the script and the execution will start. User will be able to find the backup files created in Robot Automation and Wave Server.



c. The configured paths in Robot and Wave server will contain the backup files inside the folder named by execution timestamp.





44. Configuring Copy Script

User will be able to configure the values for Database Copy script for project name and test id.

In the Copy script the user will be able enter values for two tags.

- a. Project Name User configurable project name in which the user wants to add the specific set of test cases that they want to execute instead of the whole set.
 The Project Name will be entered in the database for later use.
- b. **Test Case ID –** The user will be able to enter One Test ID from the wifi_test_param_table" in results schema that has been auto generated for the test case that he needs to copy.


#Method in Library	Project Name	Test Case ID		
MySQL_Copy	My PROJECT	3		

				_		,					
	test_id	date_ts	test_name	test_type	ssid	pw	directory	ар	apver	direction	chann
١	1	20170519-122527	AC-TP-80MHz4	TP	BELL368	testtest	C:\WifiResults\HH3000\Rel1_2_3\BELL368\TP\DS	HH3000	Rel1_2_3	DS	44
	2	20170519-131317	AC-TP-80MHz4	TP	BELL368	testtest	C:\WifiResults\HH3000\Rel1_2_3\BELL368\TP\US	HH3000	Rel1_2_3	US	44
П	3	20170519-143634	AC-RR-80MHz1	RR	BELL368	testtest	C:\WifiResults\HH3000\Rel1_2_3\BELL368\RR\DS	HH3000	Rel1_2_3	DS	44
ш											
	7	20170315-173030	AC-KK-00M121	KK.	DELEGOO	testtest	C. Willikesdits VIII 3000 (Keit_2_3 (pttt 300 (KK (p3	1113000	Kel1_2_5	03	77
*	NULL	NULL	NULL	HULL	HULL	NULL	MULL	NULL	NULL	NULL	NULL





45. Executing Copy Script

a. User will be able to execute the Copy Script by selecting the checkbox for the Backup script and after the configuration of the values have been completed.



b. Click on Run button after choosing the script and the execution will start.
 User will be able to find the copied data in the database under master schema








46. Database Backup


User will be able to find the database backup in Wave Automation Server after the execution of database backup script has been completed.

The user needs to configure the folder where the backup should be stored in the RIDE GUI. The user also needs to create the folder structure in the Wave Server. When the execution takes place, the backup files will be stored under the configured folder. A new folder will be created under the parent structure by the latest timestamp value where the backup files will be present



Automatic Backup Logs:

- a. The automatic backup task will execute as per the scheduled task that has been created.
- b. The scheduled task when execute will create a folder as shown above to create and store the database backup files.
- c. User will also be able to find the execution logs of the automatic scheduled task in **Bell_HomeHub_Automation\Bell_HomeHub_Automation_Results** folder.
- d. User will be able to find the success/ failure logs in file named in format **Backup<YYYYMMDD-HHMMSS>.log**.





47. MySQL Database Management

There can be multiple user accounts defined for accessing the database based on the rights defined for them. For example, we can create a user as shown below who will not delete rights for the data present in the tables.

- a. Login using 'root' id and create new user for automation.
- b. On the Workbench, click "Users and Privileges".




c. Click on Add Account.




d. Enter details for new user as "autotest1" in the login name field.






e. Assign the permissions and access levels for the user as **INSERT**, **CREATE**, **UPDATE**.





f. Now the user can view the tables and right-click on any row to delete the contents of the row. Click on **Delete Row(s)** option on the drop down.




g. Click on Apply button




h. Click on Apply button again.






i. The user will get to see the error message and will not be able to perform the action as the privileges have not been set.






48. MySQL Script Execution Progress

- a. The user can choose a test suite by clicking on it. As it expands the test cases in it will be visible.
- b. The user then can choose the test case to run by clicking on the checkbox and click Run to start execution as mentioned in previous sections.



c. As the execution starts, the user will be able to see the execution progress.
The upper part of the screen will show the name of the test suite being executed.
The lower part will show the execution progress logs that will be printed along with the execution steps.






49. MySQL Script Post Execution Logs

The post execution logs will be visible to the user on the screen in RIDE GUI and in a log file created for the steps executed.

a. The post execution logs as visible in the RIDE GUI will be present on the lower part of the screen as **message logs**.

Note: If the **Show message log** option is not checked, the user will not be able to see the logs on the RIDE GUI screen.



The user will also be able to see the post execution logs by clicking on Log in RIDE GUI.





c. As the user clicks, the log file will open in the default browser set for the system.

